

**Changed Pages**

**Part III, Appendix III-D.5-4**

**Landfill Foundation Settlement, Waste Settlement, and Soil Liner Strain  
Analyses**


**APPENDIX III-D.5-4**

**LANDFILL FOUNDATION SETTLEMENT,  
WASTE SETTLEMENT, AND SOIL LINER STRAIN ANALYSES**



*Michael W. Oden*  
*8-15-2017*

This document is released for the purpose of permitting only under the authority of Michael W. Oden, P.E. #67165. It has been Updated in August 2017 to match the current landfill configuration. It is not to be used for bidding or construction. Texas Registered Engineering Firm F-5650.



*J. Varsho* *3-2-15*

This document is released for the purpose of permitting only under the authority of Jesse P. Varsho, P.E. #114074. It is not to be used for bidding or construction. Texas Registered Engineering Firm F-5650

Appendix III-D.5-4, Landfill Foundation Settlement, Waste Settlement, and Liner Strain Analyses

- Updated calculations to match new landfill geometry



<b>Client Name:</b> Rancho Viejo Waste Management, LLC		
<b>Project Name:</b> Pescadito Environmental Resource Center	<b>Project No.:</b> 155145	
<b>Modified by:</b> O. Covert	<b>Date Modified:</b> 8/1/17	
<b>Reviewed by:</b> P. Thomas	<b>Date Reviewed:</b> 8/7/17	

**TITLE: LANDFILL FOUNDATION SETTLEMENT, WASTE SETTLEMENT, AND SOIL LINER STRAIN ANALYSES**

### Problem Statement

Determine the consolidation settlement of 1) the landfill foundation, and 2) the waste; and determine the strain on the soil liner due to the foundation settlement. The consolidation due to waste placement at critical locations is evaluated to determine the differential settlement between these locations. The calculations are performed to demonstrate that the leachate collection system will maintain a positive slope, and the final cover system and soil liner will not be damaged due to differential settlement.

### References

The referenced literature cited below is provided in the attached pages. Referenced site specific information is provided within the Application as stated below.

1. Mass excavation grades, liner grades, and final landform grades presented on plan drawings contained in Design Drawing Set of this Application.
2. Summary of Geotechnical Design Parameters contained in **Appendix III-D.5-1** of this Report.
3. The site Geology Report (dated 2015) contained in this Application — as it pertains to subsurface investigative data (i.e., potentiometric levels) refer to Appendix III-E.1 of the Geology Report.
4. Figures 1 and 2 presenting locations of analyzed settlement points (attached pages).
5. Microsoft Excel foundation and waste settlement calculation spreadsheets (attached pages).
6. Coduto, Donald P. (2001). "Foundation Design Principles and Practices." Prentice-Hall, 2<sup>nd</sup> Edition, 2001.
7. Sharma, H.D., and Anirban, D. (2007). "Municipal Solid Waste Landfill Settlement: Postclosure Perspectives." Journal of Geotechnical and Geoenvironmental Engineering, 133(6), 619-629.
8. Qian, X., Koerner, R.M., and Gray, D.H. (2002). "Geotechnical Aspects of Landfill Design and Construction. Prentice-Hall, 2001.


### Assumptions

#### *Locations Analyzed for Foundation Settlement*

To analyze potential impacts due to differential settlement of the landfill liner / leachate collection system, locations of where the largest differential settlement would occur were evaluated. From this evaluation, the largest differential settlement of the landfill liner system / foundation is expected to occur in the South Unit landfill between foundation settlement points **F1** and **F2** (as shown on **Figure 1** in **Reference No. 4**) for the following reasons:

- Foundation settlement point **F1** is located over the maximum waste column over the leachate collection pipe and point **F2** is located where the minimum waste column thickness occurs over the leachate collection pipe; and
- Foundation settlement point **F1** is located just south of the maximum elevation for the final landform and point **F2** is located where the lowest elevation for the leachate collection system grades occurs.

Settlement point **F1** is located approximately **214 feet west** of settlement point **F2**. The base elevation difference of the two settlement points is controlled by the **0.50%** gradient leachate pipe run (see Drawing No. III-D.3-1).

	<b>Client Name:</b> Rancho Viejo Waste Management, LLC	
	<b>Project Name:</b> Pescadito Environmental Resource Center	<b>Project No.:</b> 155145
	<b>Modified by:</b> O. Covert	<b>Date Modified:</b> 8/1/17
	<b>Reviewed by:</b> P. Thomas	<b>Date Reviewed:</b> 8/7/17
<b>TITLE: LANDFILL FOUNDATION SETTLEMENT, WASTE SETTLEMENT, AND SOIL LINER STRAIN ANALYSES</b>		

**Table 1** on the following page provides the elevations of the foundation settlement points, and the elevations and thicknesses of the relevant landfill system layers. The foundation settlement point locations are presented on **Figure 1 (Reference No. 4)**.

The leachate collection system (LCS) grades will settle as the compacted low permeable soil liner settles. The analysis that follows in this section, calculates the settlement in the compressible layers beneath the LCS:

- The compacted low permeable soil liner (3-ft); and
- Native soils that lie 50-ft beneath the proposed landfill bottom (i.e., 50-ft below the compacted low permeable soil liner).

*Note, the native soils were determined to be overconsolidated (Reference No. 2) and the overburden pressure that will be due to the final landform (i.e., complete landfill build-out) at the point of maximum waste column thickness (approximately 241 feet) will be significantly less than the preconsolidation pressure that was calculated (Reference No. 2). Therefore the assumption that the native soils 50-ft beneath the landfill bottom will settle is conservative for the purposes of this settlement calculation.*

*Locations Analyzed for Waste Settlement*

To analyze potential impacts due to differential settlement on the final cover system, locations of where the largest differential settlement of the waste would occur were evaluated. From this evaluation, the largest differential settlement of waste is expected to occur between the point of maximum waste thickness and the point of minimum waste thickness (at the edge of the landfill) or:

- Maximum waste thickness of **241 feet** at waste settlement point **W1**, and
- Minimum waste thickness of **0 feet** at the edge of the landfill at waste settlement point **W2**.

The horizontal distance between the waste settlement points **W1** and **W2** is approximately **553 feet**. **Table 1** below provides the elevations of the waste settlement points, and the elevations and thicknesses of the relevant landfill system layers. The waste settlement point locations are presented on **Figure 2. (Reference No. 4)**.



**Client Name:** Rancho Viejo Waste Management, LLC

**Project Name:** Pescadito Environmental Resource Center

**Project No.:** 155145

**Modified by:** O. Covert

**Date Modified:** 8/1/17

**Reviewed by:** P. Thomas

**Date Reviewed:** 8/7/17

**TITLE: LANDFILL FOUNDATION SETTLEMENT, WASTE SETTLEMENT, AND SOIL LINER STRAIN ANALYSES**

**Table 1  
Elevations of Material Layers  
at Foundation and Waste Settlement Points**

Settlement Point Locations	Elevation of Top of Final Landform / Final Cover	Final Cover Thickness	Waste Column Thickness	Elevation of Top of Protective Soil Cover	Protective Soil Cover Thickness	Elevation of Top of Compacted Low Permeable Soil Liner	Compacted Low Permeable Soil Liner Thickness
<b>Foundation Settlement Points:</b>							
F1	703 -ft.MSL	3 -ft	241	459 -ft.MSL	2 -ft	457 -ft.MSL	3 -ft
F2	659 -ft.MSL	3 -ft	198	458 -ft.MSL	2 -ft	456 -ft.MSL	3 -ft
<b>Waste Settlement Points:</b>							
W1	703 -ft.MSL	3 -ft	241	459 -ft.MSL	2 -ft	457 -ft.MSL	3 -ft
W2	575 -ft.MSL	3 -ft	0	572 -ft.MSL	2 -ft	570 -ft.MSL	3 -ft
<b>Note:</b> Maximum waste column thickness of 241 feet (occurring near approximate center of landfill) was conservatively assumed in settlement calculations.							

*Initial Site Conditions*

**Table 2** on the following page summarizes the geologic site stratigraphy prior to landfill development. Native soils will be excavated down to mass excavation grades (i.e., bottom of compacted soil liner elevation) — specifically, to elevations **454-ft.MSL** and **453-ft.MSL** at points **F1** and **F2**, respectively. The average potentiometric surface was assumed to be at elevation **538 ft. MSL (Reference No. 3)**.

*Final Site Conditions*

**Table 2** on the following page summarizes the stratigraphy of the landfill system layers at the time of complete landfill build-out. Inside the landfill, the potentiometric surface is assumed to be at the top of the LCS drainage geocomposite or approximately 1 inch above the compacted low permeable soil liner. Materials that are below the assumed potentiometric surface are assumed to be saturated.



**Client Name:** Rancho Viejo Waste Management, LLC

**Project Name:** Pescadito Environmental Resource Center

**Project No.:** 155145

**Modified by:** O. Covert

**Date Modified:** 8/1/17


**Reviewed by:** P. Thomas

**Date Reviewed:** 8/7/17

**TITLE: LANDFILL FOUNDATION SETTLEMENT, WASTE SETTLEMENT, AND SOIL LINER STRAIN ANALYSES**

**Table 2  
Descriptions of Site Stratigraphy At Foundation Settlement Points (F1, F2)  
BEFORE and AFTER Landfill Development**

Geologic and Landfill System Layer Descriptions	Top Elevation of Layer	Thickness	Moist Unit Weight	Saturated Unit Weight
<b>At Point F1: BEFORE Landfill Development</b>				
Stratum II-III-IV (excavated, dry)	555 -ft.MSL	17 -ft	129 pcf	132 pcf
Stratum II-III-IV (excavated, saturated)	538 -ft.MSL	84 -ft	129 pcf	132 pcf
Stratum II-III-IV (compressible, saturated)	454 -ft.MSL	50 -ft	129 pcf	132 pcf
Stratum II-III-IV (incompressible, saturated)	404 -ft.MSL	-	-	-
<b>At Point F1: AFTER Landfill Development</b>				
Final Cover System	703 -ft.MSL	3 -ft	129 pcf	132 pcf
Waste Fill	700 -ft.MSL	241 -ft	65 pcf	65 pcf
Protective Soil Cover	459 -ft.MSL	2 -ft	129 pcf	132 pcf
Compacted Low Permeable Soil Liner	457 -ft.MSL	3 -ft	129 pcf	132 pcf
Stratum II-III-IV (compressible, saturated)	454 -ft.MSL	50 -ft	129 pcf	132 pcf
Stratum II-III-IV (incompressible, saturated)	404 -ft.MSL	-	-	-
<b>At Point F2: BEFORE Landfill Development</b>				
Stratum II-III-IV (excavated, dry)	556-ft.MSL	18 -ft	129 pcf	132 pcf
Stratum II-III-IV (excavated, saturated)	538 -ft.MSL	85 -ft	129 pcf	132 pcf
Stratum II-III-IV (compressible, saturated)	453 -ft.MSL	50 -ft	129 pcf	132 pcf
Stratum II-III-IV (incompressible, saturated)	403 -ft.MSL	-	-	-
<b>At Point F2: AFTER Landfill Development</b>				
Final Cover	659-ft.MSL	3 -ft	129 pcf	132 pcf
Waste	656 -ft.MSL	198 -ft	65 pcf	65 pcf
Protective Soil Cover	458 -ft.MSL	2 -ft	129 pcf	132 pcf
Compacted Low Permeable Soil Liner	456 -ft.MSL	3 -ft	129 pcf	132 pcf
Stratum II-III-IV (compressible, saturated)	453 -ft.MSL	50 -ft	129 pcf	132 pcf
Stratum II-III-IV (incompressible, saturated)	403 -ft.MSL	-	-	-

	<b>Client Name:</b> Rancho Viejo Waste Management, LLC	
	<b>Project Name:</b> Pescadito Environmental Resource Center	<b>Project No.:</b> 155145
	<b>Modified by:</b> O. Covert	<b>Date Modified:</b> 8/1/17
	<b>Reviewed by:</b> P. Thomas	<b>Date Reviewed:</b> 8/7/17
<b>TITLE: LANDFILL FOUNDATION SETTLEMENT, WASTE SETTLEMENT, AND SOIL LINER STRAIN ANALYSES</b>		

### Liner / Foundation Settlement Equations

Consolidation is divided into three categories: 1) immediate settlement, 2) primary consolidation settlement, and 3) secondary settlement. Immediate settlement is caused by the elastic deformation of soils without any change in the moisture content. Primary consolidation in saturated fine-grained soils occurs due to the expulsion of water in response to an increase in effective stress. Following primary consolidation under a constant effective stress is secondary consolidation. Primary and secondary consolidations are calculated for the compacted low permeable soil liner. It was determined that the native soils below the low permeability soil liner are overconsolidated (**Reference No. 2**).

#### Primary Settlement

For overconsolidated soils, where  $\Phi'_o < \Phi'_f \leq \Phi'_p$ , primary settlement is determined using the following equation:

$$S_p = \frac{C_r}{1 + e_o} * H * \log\left(\frac{\sigma'_f}{\sigma'_o}\right)$$

Where,

- $S_p$  = Primary Settlement, feet
- $C_r$  = Recompression Index
- $H$  = Thickness of the layer, feet
- $e_o$  = Initial void ratio
- $\sigma'_o$  = Initial vertical effective stress, psf
- $\sigma'_f$  = Final vertical effective stress, psf

Consolidation parameters have been summarized in **Appendix III-D.5-1** of this Report (**Reference No. 2**).

#### Secondary Settlement

It is conservatively assumed that primary consolidation is complete subsequent to final cover placement. Secondary consolidation is calculated using the following equation.


$$S_s = \frac{C_\alpha}{1 + e_p} * H * \log\left(\frac{T_2}{T_1}\right)$$

Where:

- $S_s$  = Secondary settlement, feet
- $C_\alpha$  = Secondary compression index
- $H$  = Thickness of Layer, feet
- $e_p$  = Void Ratio at end of primary consolidation  
=  $e_o$  (to be conservative)
- $T_1$  = Time at start of secondary compression, years
- $T_2$  = Time at end of observation period, years

Values of  $C_\alpha$  used in the settlement analyses have been summarized in **Appendix III-D.5-1** of this Report (**Reference No. 2**).



	<b>Client Name:</b> Rancho Viejo Waste Management, LLC	
	<b>Project Name:</b> Pescadito Environmental Resource Center	<b>Project No.:</b> 155145
	<b>Modified by:</b> O. Covert	<b>Date Modified:</b> 8/1/17
	<b>Reviewed by:</b> P. Thomas	<b>Date Reviewed:</b> 8/7/17

**TITLE: LANDFILL FOUNDATION SETTLEMENT, WASTE SETTLEMENT, AND SOIL LINER STRAIN ANALYSES**

**Final Cover / Waste Settlement Equations**

The waste settlement calculations are based on Terzaghi's theory of one-dimensional consolidation in which the primary settlement, time of primary settlement, and secondary settlement are evaluated. However waste will not experience primary consolidation in the manner of a saturated soil. Waste will undergo initial and primary compression. Both types of compression occur rapidly and are grouped together. The primary settlement is calculated incrementally for nineteen (19) fill lifts of waste and one lift for the final cover placement for one landfill cell. It is assumed that each lift of waste is 20-feet thick and each lift will take 3 months to complete. The estimate for primary settlement assumes that as each lift (or load) is placed large settlements will occur rapidly with no pore pressure build up.

The time of primary compression is estimated to be completed within 2 to 30 days following loading. From this estimate, we can assume that the final cover will only be subjected to the primary settlement from the final lift of the landfill plus secondary settlement that will occur during post-construction / post-closure. The waste settlement calculations focus on the post-closure settlement to evaluate the potential for damage to the final cover system.

The secondary settlement was calculated based on Terzaghi's time-settlement relationship. Because it is assumed that secondary settlement occurs by the self-weight of each fill lift, the secondary settlement is calculated for each lift individually, and then summed to provide a total value for secondary settlement.

**Liner / Foundation Settlement Calculations**

The equations presented on the previous page were used to estimate the foundation settlement at Points **F1** and **F2**. The thickness of waste at points **F1** and **F2** are **241 feet** and **198 feet**, respectively. The final effective overburden stress and settlement vary accordingly.

Initial Effective Stress. The initial effective stress of the in-situ materials is the average effective stress prior to excavation and waste placement. The initial effective stress for the compacted low permeable soil liner was calculated as the weight of itself. The effective stress is calculated at the center of each geologic unit / layer (please refer to the attached spreadsheets for calculations, provided as **Reference No. 5**).

Final Effective Stress. The final effective stress is the effective stress following final cover placement and varies for settlement points **F1** and **F2**. The effective stress is calculated at the center of each geologic unit / layer (please refer to the attached spreadsheets for calculations, provided as **Reference No. 5**). The effective stress values for initial and final conditions, for each geologic / landfill layer are summarized on **Tables 3** and **4** on the following page.





<b>Client Name:</b>	Rancho Viejo Waste Management, LLC		
<b>Project Name:</b>	Pescadito Environmental Resource Center	<b>Project No.:</b>	155145
<b>Modified by:</b>	O. Covert	<b>Date Modified:</b>	8/1/17
<b>Reviewed by:</b>	P. Thomas	<b>Date Reviewed:</b>	8/7/17

**TITLE: LANDFILL FOUNDATION SETTLEMENT, WASTE SETTLEMENT, AND SOIL LINER STRAIN ANALYSES**

Table 3 Initial and Final Effective Stresses				
Geologic Unit / Landfill Layer	Initial Effective Stress		Final Effective Stress	
	Point F1	Point F2	Point F1	Point F2
Compacted Low Permeable Soil Liner	104.4 psf	104.4 psf	16,191.7 psf	13,630.1 psf
Stratum II-III-IV	9,779.4psf	9,978.0 psf	18,269.5 psf	15,474.5 psf

*Primary and Secondary Consolidation Settlement*

**Table 4** below summarizes the calculated settlement at foundation settlement points F1 and F2. Detailed spreadsheets providing a breakdown of the calculations are provided in the attached pages (**Reference No. 5**).

Table 4 Liner / Foundation Settlement			
Landfill Layer	Primary Settlement	Secondary Settlement	TOTAL Settlement
<b>Settlement at Point F1:</b>			
Compacted Low Permeable Soil Liner	0.244101422 -ft	0.018588267 -ft	0.262689689 -ft
Stratum II-III-IV	0.503937507 -ft	0.309804455 -ft	0.813741962-ft
<b>TOTAL:</b>	<b>0.748038929 -ft</b>	<b>0.3289392722 -ft</b>	<b>1.076431652-ft</b>
<b>Settlement at Point F2:</b>			
Compacted Low Permeable Soil Liner	0.235767069 -ft	0.018588267 -ft	0.254355336 -ft
Stratum II-III-IV	0.353931844 -ft	0.309804455 -ft	0.663736299 -ft
<b>TOTAL:</b>	<b>0.589698913 -ft</b>	<b>0.328392722 -ft</b>	<b>0.918091636 -ft</b>

Total Liner / Foundation Settlement. The total settlement of the foundation soils is equal to the summation of the settlement of each geologic unit. The elevation of the top of the compacted low permeability soil liner after settlement will be approximately:

- At Settlement Point F1: (EL. 457-ft MSL) - (1.076431652-ft) = **EL.455.924-ft MSL**
- At Settlement Point F2: (EL. 456-ft MSL) - (0.918091636-ft) = **EL. 455.082-ft MSL**



**Client Name:** Rancho Viejo Waste Management, LLC

**Project Name:** Pescadito Environmental Resource Center

**Project No.:** 155145

**Modified by:** O. Covert

**Date Modified:** 8/1/17

**Reviewed by:** P. Thomas

**Date Reviewed:** 8/7/17

**TITLE: LANDFILL FOUNDATION SETTLEMENT, WASTE SETTLEMENT, AND SOIL LINER STRAIN ANALYSES**

*Differential Settlement*

The differential settlement between Points **F1** and **F2** are calculated as follows:

$$S_{diff} = \frac{|S_{pt.F1} - S_{pt.F2}|}{Horizontal\ Distance_{pt.F1/pt.F2}} \times 100\%$$

$$S_{diff} = \frac{|1.076431652\ ft - 0.918091636\ ft|}{214\ ft} = 0.07399\%$$

*Slope of Leachate Collection System*

The leachate collection system (LCS) is designed with a **slope of 0.50%** (slope along LCS collection pipe). During waste placement and post-closure care, differential settlement will occur. At the end of the post-closure care period, the final slope between points **F1** and **F2** will be:

$$Slope_{diff} = \frac{Elev_{pt.F1} - Elev_{pt.F2}}{Horizontal\ Distance_{pt.F1/pt.F2}} \times 100\%$$

$$Slope_{diff} = \frac{(455.924\ ft - 455.082\ ft)}{214\ ft} \times 100\% = 0.39346\%$$

*Compacted Low Permeable Soil Liner Strain*

The maximum strain ( $\epsilon$ ) the compacted low permeable soil liner will experience from the foundation settlement will be equal to **0.0003178%** which is deemed within acceptable limits for a compacted clay soil, and therefore the soil liner integrity will not be compromised due to cracking (**Reference No. 8**).

$$\epsilon_{F1,F2} = \frac{|(L_{F1,F2})_{Final} - (L_{F1,F2})_{Initial}|}{(L_{F1,F2})_{Initial}} \times 100\%$$

$$(L_{F1,F2})_{Initial} = \sqrt{(El.\ 457\ ft - El.\ 456\ ft)^2 + (214\ ft)^2} = 214.002336\ ft$$

$$(L_{F1,F2})_{Final} = \sqrt{(El.\ 455.924\ ft - El.\ 455.082\ ft)^2 + (214\ ft)^2} = 214.001656\ ft$$

$$\epsilon_{F1,F2} = \frac{|(214.001656\ ft) - (214.002336\ ft)|}{(214.002336\ ft)} \times 100\%$$

$$\epsilon_{F1,F2} = 0.0003178\%$$



<b>Client Name:</b>	Rancho Viejo Waste Management, LLC		
<b>Project Name:</b>	Pescadito Environmental Resource Center	<b>Project No.:</b>	155145
<b>Modified by:</b>	O. Covert	<b>Date Modified:</b>	8/1/17
<b>Reviewed by:</b>	P. Thomas	<b>Date Reviewed:</b>	8/7/17

**TITLE: LANDFILL FOUNDATION SETTLEMENT, WASTE SETTLEMENT, AND SOIL LINER STRAIN ANALYSES**

A summary of the differential settlement, soil liner strain, and the initial and final LCS slopes between the foundation settlement point locations analyzed (i.e., F1 and F2) is presented below on **Table 5**.

Table 5 Summary of Foundation Differential Settlement, Initial and Final LCS Slopes, and Soil Liner Strain				
Location	Foundation Differential Settlement	Initial LCS Slope	Final LCS Slope	Compacted Low Permeable Soil Liner Strain
Between Settlement Points F1 and F2	0.07399%	0.5%	0.39346%	0.0003178%

### Final Cover / Waste Settlement Calculations

The calculated settlement at settlement point **W1** is calculated to be approximately **27.54 feet** (refer to attached spreadsheets in **Reference No. 5**):

$$S_{pt.W1} = (\Delta S_p \text{ due to Final Cover Placement}) + (3S_s \text{ following post construction, 30yrs.})$$

$$S_{pt.W1} = (1.10ft + 26.44ft) = 27.54ft$$

Differential settlement between points **W1** and **W2** was calculated using a value of **27.54 feet**. At point **W2**, settlement is **0 feet**; therefore, the differential settlement between Points **W1** and **W2** is approximately **4.98 percent**:

$$S_{diff} = \frac{|S_{pt.W1} - S_{pt.W2}|}{Distance_{pt.W1/pt.W2}} \times 100\%$$

$$S_{diff} = \frac{|27.54 ft - 0.00 ft|}{553 ft} = 4.98\%$$

### Results

#### Foundation Settlement


The estimated maximum differential settlement of the landfill foundation is approximately 0.0007399 ft/ft. This settlement value is deemed negligible and will not cause failure of the liner or leachate collection system. The slope of the leachate collection system at the end of the post-closure care period will be approximately 0.39% which will allow for proper leachate drainage and collection.

#### Waste Settlement

The estimated maximum differential settlement of the landfill final slopes due to waste settlement is approximately 0.0498 ft/ft. This value is considered to be negligible and will not cause or contribute to the failure of the final cover system.

**Reference No. 4**

Figures 1 and 2



**PESCADITO ENVIRONMENTAL RESEARCH CENTER  
WEBB COUNTY, TEXAS (MSW 2374)**

**APPENDIX III-D.5-4, FIGURE 1  
LOCATION OF FOUNDATION SETTLEMENT POINTS  
SHOWN ON TOP OF MASS EXCAVATION GRADES**

DRAWN BY: ORC APPROVED BY: MWO PROJ. NO.: 155145 DATE: AUGUST 2017

**APTIM Environmental  
& Infrastructure, Inc.**




(Use CSR&I Environmental & Infrastructure, Inc.)  
TYPE PERMITS  
APTIM Environmental & Infrastructure, Inc. has prepared this document for a specific project or purpose. All information contained within this document is copyrighted and remains the intellectual property of APTIM Environmental & Infrastructure, Inc. This document may not be used or copied, in part or in whole, for any purpose without express written consent by APTIM Environmental & Infrastructure, Inc.



*Actual w/ elev  
for Permittions  
Only*

*8/15-2017*



STATE OF TEXAS  
 MICHAEL W. ODEN  
 67165  
 REGISTERED PROFESSIONAL ENGINEER

*For Permitting Only*  
 8-15-2017

*Michael W. Oden*



APTIM Environmental & Infrastructure, Inc.  
 (Formerly CS&I Environmental & Infrastructure, Inc.)  
 TBPPE FIRM F-5850

APTIM Environmental & Infrastructure, Inc. has prepared this document for a specific project or purpose. All information contained within this document is copyrighted and remains intellectual property of APTIM Environmental & Infrastructure, Inc. This document may not be used or copied, in part or in whole, for any other project without express written consent by APTIM Environmental & Infrastructure, Inc.

**PESCADITO ENVIRONMENTAL RESEARCH CENTER  
 WEBB COUNTY, TEXAS (MSW 2374)**

**APPENDIX III-D.5-4, FIGURE 2  
 LOCATION OF WASTE SETTLEMENT POINTS  
 SHOWN ON TOP OF FINAL LANDFILL GRADES**

DRAWN BY:	ORC	APPROVED BY:	MWO	PROJ. NO.:	155145	DATE:	AUGUST 2017
-----------	-----	--------------	-----	------------	--------	-------	-------------

## Reference No. 5

### Foundation and Waste Settlement Calculation Spreadsheets



*Michael W. Oden*  
8-15-2017

This document is released for the purpose of permitting only under the authority of Michael W. Oden, P.E. #67165. It has been Updated in August 2017 to match the current landfill configuration. It is not to be used for bidding or construction. Texas Registered Engineering Firm F-5650.



*J. Varsho* 3-2-15

This document is released for the purpose of permitting only under the authority of Jesse P. Varsho, P.E. #114074. It is not to be used for bidding or construction. Texas Registered Engineering Firm F-5650

Appendix III-D.5-4, Landfill Foundation Settlement, Waste Settlement, and Liner Strain Analyses

- Updated calculations to match new landfill geometry

# Settlement Point F1

(Page 1 of 3)

Stress concentrations through cross section of a Landfill

Company Name  
Project Name  
Project Number  
Date

APTIM  
Pescadito Landfill  
155145  
7/26/2017

Make sure that the cross sections for both the before and after landfill line up at the bottom geological units under the landfill liner.

Units

English

## Cross Section before landfill development Settlement Point F1

Unit	Classification	Interval	Thickness (ft)	Relative Density (%)	Unit Weights (pcf)		Mid-Layer Stresses (psf)		Bottom-Layer Stresses (psf)	
					ysat	ybuoyant	$\sigma'$ (effective)	$\sigma$ (total)	$\sigma'$ (effective)	$\sigma$ (total)
Example	EX	0-2	2		0	0	0.00	0.00	0.00	0.00
Stratum II-III-IV (excavated, dry)	CH	El. 555-538	17		129	129	1,096.50	1,096.50	2,193.00	2,193.00
Stratum II-III-IV (excavated, saturated)	CH	El. 538-454	84		132	69.6	5,116.20	7,737.00	8,039.40	13,281.00
Stratum II-III-IV (compressible, saturated)	CH	El. 454-404	50		132	69.6	9,779.40	16,581.00	11,519.40	19,881.00
Stratum II-III-IV (incompressible, saturated)	CH	El. 404-								



# Settlement Point F1

(Page 2 of 3)

Stress concentrations through cross section of a Landfill

Company Name	APTIM
Project Name	Pescadito Landfill
Project Number	155145
Date	7/26/2017

Units English

### Cross Section after Landfill Settlement Point F-1

Unit	Classification	Interval	Thickness (ft)	Unit Weights (pcf)		Mid-Layer Stresses (psf)		Bottom-Layer Stresses (psf)	
				ysat	ybuoyant	$\sigma'$ (effective)	$\sigma$ (total)	$\sigma'$ (effective)	$\sigma$ (total)
Example	EX	0-2	2	0	0	0.00	0.00	0.00	0.00
Final Cover	CH	El. 703-700	3.083	129	129	198.85	198.85	397.71	397.71
Waste	-	El. 700-459	241	65	65	8,230.21	8,230.21	16,062.71	16,062.71
Protective Cover Soil	CH	El. 459-457	2	129	129	16,191.71	16,191.71	16,320.71	16,320.71
Compacted Low Permeable Soil Liner	CH	El. 457-454	3	132	69.6	16,425.11	16,518.71	16,529.51	16,716.71
Stratum II-III-IV (compressible, saturated)	CH	El. 454-404	50	132	69.6	18,269.51	20,016.71	20,009.51	23,316.71
Stratum II-III-IV (incompressible, saturated)	CH	El. 404-							

# Settlement Point F1

(Page 3 of 3)

Settlement Analysis for the base of a Landfill

Enter data into the necessary white cells  
Data must be entered into all the columns that contain comments

Units English

Method for Non-Cohesive Soils  
Mark X in the correct box

Classical	<input checked="" type="checkbox"/>
Peck	<input type="checkbox"/>

Life of Landfill (Yrs) 5.5

Post-closure care period + Life of Landfill (Yrs) 36.5

Total Settlement (ft) 1.07643

Company Name APTIM

Project Name Pescadito Landfill

Project Number 155145

Date 7/26/2017

Settlement Point F1 Unit	Classification	Cohesion or Non-Cohesion	Interval	Thickness (ft)	Liquid Limit	Corrected Standard Penetration Count	Void Ratio	Compression Index	Recompression Index	Secondary Compression Index	Preconsolidation Stress (psf)	Mid-Layer Stresses (psf)	Settlement		
													σ' (initial)	σ' (final)	Primary Settlement
Example	EX	C	0-2	2	LL	N60	e <sub>0</sub>	Cc	Cr	Ca	σ' c	σ' (initial)	σ' (final)	0	0.000000
Compacted Low Permeable Soil Liner	CH	C	El. 457-454	3	58		0.64	0.0609	0.0609	0.0136	-	104.40	16,191.71	0.244101422	0.018568267
Stratum II-II-IV (compressible, saturated)	CH	C	El. 454-404	50	58		0.64	0.4240	0.0609	0.0136	114,763.00	9,779.40	18,269.51	0.503937507	0.262689689
Stratum II-II-IV (incompressible, saturated)	CH	C	El. 404-											0.309804455	0.813741962

Settlement<sub>liner</sub> = 0.244101422 0.018568267 0.262689689  
 Settlement<sub>subgrade</sub> = 0.503937507 0.309804455 0.813741962  
**Totals = 0.748038929 0.328392722 1.076431652**

**Note:**  
The compression index (Cc) for the low permeable soil liner was set equal to the recompression index (Cr) since there is no preconsolidation stress.



# Settlement Point F2

(Page 4 of 3)

## Stress concentrations through cross section of a Landfill

Company Name  
 Project Name  
 Project Number  
 Date

APTIM  
 Pescadito Landfill  
 155145  
 7/26/2017

Make sure that the cross sections for both the before and after landfill line up at the bottom geological units under the landfill liner.

Units

English

## Cross Section before landfill Settlement Point F2

Unit	Classification	Interval	Thickness (ft)	Relative Density (%)	Unit Weights (pcf)		Mid-Layer Stresses (psf)		Bottom-Layer Stresses (psf)	
					ysat	ybuoyant	$\sigma'$ (effective)	$\sigma$ (total)	$\sigma'$ (effective)	$\sigma$ (total)
Example	EX	0-2	2		0	0	0.00	0.00	0.00	0.00
Stratum II-III-IV (excavated, dry)	CH	El. 556-538	18		129	129	1,161.00	1,161.00	2,322.00	2,322.00
Stratum II-III-IV (excavated, saturated)	CH	El. 538-453	85		132	69.6	5,280.00	7,932.00	8,238.00	13,542.00
Stratum II-III-IV (compressible, saturated)	CH	El. 453-403	50		132	69.6	9,978.00	16,842.00	11,718.00	20,142.00
Stratum II-III-IV (incompressible, saturated)	CH	El. 403-								

# Settlement Point F2

(Page 5 of 3)

Stress concentrations through cross section of a Landfill

Company Name	APTIM
Project Name	Pescadito Landfill
Project Number	155145
Date	7/26/2017

Units English

**Cross Section after development of landfill  
Settlement Point F2**

Unit	Classification	Interval	Thickness (ft)	Unit Weights (pcf)		Mid-Layer Stresses (psf)		Bottom-Layer Stresses (psf)	
				ysat	ybuoyant	$\sigma'$ (effective)	$\sigma$ (total)	$\sigma'$ (effective)	$\sigma$ (total)
Example	EX	0-2	2	0	0	0.00	0.00	0.00	0.00
Final Cover	CH	EL. 659-656	3.083	129	129	198.85	198.85	397.71	397.71
Waste	-	EL. 656-458	198	65	65	6,832.71	6,832.71	13,267.71	13,267.71
Protective Cover Soil	CH	EL. 458-456	2	129	129	13,396.71	13,396.71	13,525.71	13,525.71
Compacted Low Permeable Soil Liner	CH	EL. 456-453	3	132	69.6	13,630.11	13,723.71	13,734.51	13,921.71
Stratum II-III-IV (compressible, saturated)	CH	EL. 453-403	50	132	69.6	15,474.51	17,221.71	17,214.51	20,521.71
Stratum II-III-IV (incompressible, saturated)	CH	EL. 403-							

# Settlement Point F2

(Page 3 of 3)

Settlement Analysis for the base of a Landfill

Enter data into the necessary white cells  
Data must be entered into all the columns that contain comments

Units English

Life of Landfill (yrs) 6.5

Post-closure care period + Life of Landfill (yrs) 36.5

Total Settlement (ft) 0.91809

Method for Non-Cohesive Soils  
Mark X in the correct box

Classical	X
Peck	

Company Name  
APTIM

Project Name  
Pescadito Landfill

Project Number  
148866

Date  
7/26/2017

Settlement Point F2	Unit	Classification	Cohesion or Non-Cohesion	C or N	Interval	Thickness (ft)	Liquid Limit	Corrected Standard Penetration Count	Void Ratio	Compression Index	Cc	Cr	Ca	Preconsolidation Stress (psf)	σ' (initial)	σ' (final)	Mid-Layer Stresses (psf)	Mid-Layer Stresses (psf)	Primary Settlement	Secondary Settlement	Settlement
Example		EX	C	N	0-2	2	LL	N60	e <sub>o</sub>	Cc	Cr	Ca		σ'c	σ' (initial)	σ' (final)					
Compacted Low Permeable Soil Liner		CH	C	C	EI 456-453	3	58		0.64	0.0609	0.0609	0.0136	0.0136	-	104.40	13,630.11	0.235767089	0.018588267	0.235767089	0.018588267	0.254355336
Stratum II-III-IV (compressible, saturated)		CH	C	C	EI 453-403	50	58		0.84	0.4204	0.0609	0.0609	0.0136	114,763.00	9,978.00	15,474.51	0.353931844	0.309804455	0.353931844	0.309804455	0.663736299
Stratum II-III-IV (incompressible, saturated)		CH	C	C	EI 403-																

Settlement<sub>liner</sub> = 0.235767089 0.018588267 0.254355336  
 Settlement<sub>surgrade</sub> = 0.353931844 0.309804455 0.663736299  
 Totals = 0.689698913 0.328392722 0.918091636

**Note:**  
The compression index (Cc) for the low permeable soil liner was set equal to the recompression index (Cr) since there is no preconsolidation stress.



<b>Given:</b>	
<b>Primary Settlement Eqtn.</b>	$S_p = H \times C'_c (\log (\sigma'_{z0} + \sigma'_{zf}) / \sigma'_{z0})$
	$C'_c = 0.25$ $H_{waste}$ = height of waste fill lift Maximum waste height of cell = 241 feet Waste is placed in twelve (12) lifts at 20 feet each and one lift at 1 foot $Y_{waste}$ (pcf) = 65 Each lift takes 3 months to complete
<b>Final Cover</b>	$H_{final\ cover}$ (ft) = 3 $Y_{final\ cover}$ (pcf) = 129 Assume 3 months to complete construction of final cover
<b>Stresses</b>	$\sigma'_{z0}$ = initial effective stress (psf) $\sigma'_{zf}$ = final effective stress (psf)
<b>Other Information</b>	Each lift takes 3 months to complete (conservative) Life of landfill is assumed to be 6.5 years

Placement of Lift (mos.)	Lift No.	Depth of Fill Lift (ft)	Total Depth of Fill (ft)	Mid-Lift Stresses (psf)																												Total Primary Settlement "S <sub>p</sub> " (ft)	Incremental Primary Settlement "S <sub>p</sub> " (ft)
				Lift 1	Lift 2	Lift 3	Lift 4	Lift 5	Lift 6	Lift 7	Lift 8	Lift 9	Lift 10	Lift 11	Lift 12	Lift 13	Lift 14																
				$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$	$\sigma'_{z0}$	$\sigma'_{zf}$				
3	1	20	20	650	650	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.00					
6	2	20	40	650	1,300	650	650	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.51	1.51				
9	3	20	60	650	1,950	650	1,300	650	650	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3.89	3.01				
12	4	20	80	650	2,600	650	1,950	650	1,300	650	650	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	6.90	3.49				
15	5	20	100	650	3,250	650	2,600	650	1,950	650	1,300	650	650	-	-	-	-	-	-	-	-	-	-	-	-	-	-	10.40	3.89				
18	6	20	120	650	3,900	650	3,250	650	2,600	650	1,950	650	1,300	650	650	-	-	-	-	-	-	-	-	-	-	-	-	14.29	4.23				
21	7	20	140	650	4,550	650	3,900	650	3,250	650	2,600	650	1,950	650	1,300	650	650	-	-	-	-	-	-	-	-	-	-	18.51	4.52				
24	8	20	160	650	5,200	650	4,550	650	3,900	650	3,250	650	2,600	650	1,950	650	1,300	650	650	-	-	-	-	-	-	-	-	23.03	4.77				
27	9	20	180	650	5,850	650	5,200	650	4,550	650	3,900	650	3,250	650	2,600	650	1,950	650	1,300	650	650	-	-	-	-	-	-	27.80	5.00				
30	10	20	200	650	6,500	650	5,850	650	5,200	650	4,550	650	3,900	650	3,250	650	2,600	650	1,950	650	1,300	650	650	-	-	-	-	32.80	5.21				
33	11	20	220	650	7,150	650	6,500	650	5,850	650	5,200	650	4,550	650	3,900	650	3,250	650	2,600	650	1,950	650	1,300	650	650	-	-	38.01	5.40				
36	12	20	240	650	7,800	650	7,150	650	6,500	650	5,850	650	5,200	650	4,550	650	3,900	650	3,250	650	2,600	650	1,950	650	1,300	650	650	43.40	0.33				
39	13	1	241	650	7,833	650	7,183	650	6,533	650	5,883	650	5,233	650	4,583	650	3,933	650	3,283	650	2,633	650	1,983	650	1,333	650	683	43.73	1.10				
42	final cover	3.000	244.000	650	7,930	650	7,280	650	6,630	650	5,980	650	5,330	650	4,680	650	4,030	650	3,380	650	2,730	650	2,080	650	1,430	650	780	44.84	(Σ S <sub>p</sub> = 44.84)				

Notes:  
Incremental settlement is the difference of the total primary settlement number and the previous total primary settlement number.

**Pescadito Landfill - Secondary Waste Settlement Calculation  
August 2017**

<b>Given:</b>	
<b>Waste</b>	<p><b>Secondary Settlement Eqtn: <math>S_s = [(C'_\alpha) * (H_o) * (\log (t_2 / t_1))]</math></b>  <math>C'_\alpha = 0.051</math>                  Maximum height of cell = 241 ft. (waste) + 3 ft. (cover) = 244 ft.                  Waste is placed in twelve (12) lifts at 20 ft. each and one lift at one foot  <math>H_o =</math> height of lifts 1-12 = 20 feet lift 13 = 1 feet                  Assume 3 months to complete each lift: <math>t_1 = 0.25</math> yrs</p>
<b>Final Cover</b>	<p><b>Secondary Settlement Eqtn: <math>S_s = [(C_o) / (1+e_o)] * (H_o) * (\log (t_2 / t_1))]</math></b>  <math>e_o = 0.064</math>  <math>C_o = 0.0136</math>  <math>H_o =</math> height of final cover = 3 feet                  Assume 3 months to complete construction of final cover</p>
<b>Other Information</b>	<p>Landfill life conservatively assumed = 6.5 years                  Post Closure monitoring period = 30 years  <math>t_1 =</math> time of pseudo-primary settlement to occur after completion of fill (years)  <math>t_2 =</math> time after placed fill and post-closure (years) = ( 30 + 30 - (<math>\sum t_x</math>) )</p>

Lift No.	(A) Total Time in Months to Complete Filling of Lifts	(B) Total Time in Years to Complete Filling of Lifts ( $\sum t_x$ )	(C) $t_1$ (yrs)	(D) $t_2$ (yrs)	$t_2 / t_1$	$S_s$ (ft)
1	3	0.25	0.25	36.25	145	2.205
2	6	0.50	0.25	36.00	144	2.202
3	9	0.75	0.25	35.75	143	2.198
4	12	1.00	0.25	35.50	142	2.195
5	15	1.25	0.25	35.25	141	2.192
6	18	1.50	0.25	35.00	140	2.189
7	21	1.75	0.25	34.75	139	2.186
8	24	2.00	0.25	34.50	138	2.183
9	27	2.25	0.25	34.25	137	2.179
10	30	2.50	0.25	34.00	136	2.176
11	33	2.75	0.25	33.75	135	2.173
12	36	3.00	0.25	33.50	134	2.170
13	39	3.25	0.25	33.25	133	0.108
final cover	42	3.50	0.25	33.00	132	0.081
<b><math>\sum</math> Settlement =</b>						<b>26.44</b>

Notes:

- (A) = 3 months + time for filling previous lifts
- (B) = Col.(A) / 12
- (C) = (3 mos.) x (1 yr./12mos.) = 0.25
- (D) = 30 + 30 - Col.(B)