Part III Attachment III-J

COST ESTIMATES FOR CLOSURE AND POST-CLOSURE CARE

Pescadito Environmental Resource Center MSW No. 2374 Webb County, Texas



Initial Submittal March 2015 Revised September 2015

Revised August 2016

Prepared For: Rancho Viejo Waste Management, LLC 1116 Calle del Norte Laredo, TX 78041

> Prepared by: CB&I Environmental and Infrastructure, Inc.

12005 Ford Rd, Suite 600 Dallas, TX 75234 This document is released for the purpose of permitting only under the authority of David R. Friels, P.E. #51700. It is not to be used for bidding or construction. Texas Registered Engineering Firm F-5650

Table of Contents

1.0)	INTRODUCTION	. 1
2.0)	Closure and Post-Closure Care Costs	.3
	2.1	Closure Costs	.3
	2.2	Post-Closure Costs	.3
3.0)	Closure and Post-closure Care Cost Estimates	.5
4.0)	Financial Assurance And Cost Estimate Adjustments	.6
	4.1	Financial Assurance	.6
	4.2	Cost Estimate Revisions	.6

APPENDIX III-J.1

Closure and Post-Closure Care Cost Estimates

This document is released for the purpose of permitting only under the authority of David R. Friels, P.E. #51700. It is not to be used for bidding or construction. Texas Registered Engineering Firm F-5650

1.0 INTRODUCTION

The cost estimate for closure and post-closure care of the Pescadito Environmental Resource Center (PERC) has been prepared consistent with the requirements of Title 30, Chapter 330, Subchapter L. The purpose of this attachment is to provide written cost estimates for a third party to close the largest waste area of the landfill that could potentially be open and to conduct post-closure care activities in accordance with the facilities approved Closure and Post-Closure Care Plans and consistent with §330.503 and 507. Additionally, costs are included for closure of the liquid waste solidification unit and the citizen convenience center in accordance with §330.505. Costs are also provided for decommissioning and closure of the contaminated water storage facility once it is no longer required. A copy of the approved Attachment III-J, Closure and Post-Closure Care Cost Estimates will be placed in the Site Operating Record prior to receipt of waste.

The landfill waste disposal area is divided into north and south units with areas of 320.5 and 340.2 acres, respectively. The total permitted waste disposal area is 660.7 acres and permitted solid waste volume is 223,316,800 cubic yards (solid waste and daily cover). The projected solid waste capacity is 195,960,492 tons. The facility is located in an arid climate and has a permitted <u>alternate water balance (WB)</u> final cover consisting of the following (from top down):

Final Cover Layer	Class 1 Cells	Non-Class 1 Cells			
Topsoil/vegetation	7 inches	7 inches			
Soil evapotranspiration	30 inches	30 inches			
(storage)					
Geosynthetic drain	Required	Not required			
40 mil LLDPE	Required	Not required			
geomembrane					
Intermediate cover soil	12 inches	12 inches			

- 7 inches of erosion layer
- 30 inches of infiltration layer

The liquid solidification unit and citizen convenience center will require closure but will not impact post-closure care costs.

PERC will retain the right of entry and maintain all rights-of-way to the closed landfill in order to conduct site maintenance, maintain final cover, vegetation, drainage and perform corrective action and remediation as needed.

Information on contacting the responsible person is provided in Attachment III-I, Post-Closure Care Plan.

APPENDIX III-J.1

CLOSURE AND POST-CLOSURE CARE COST ESTIMATES

INITIAL SUBMITTAL MARCH 2015

REVISED SEPTEMBER 2015

REVISED AUGUST 2016

Prepared by: DRF

TOTAL CLOSURE AND POST-CLOSURE CARE COSTS										
	Closure	Post-Closure	Total							
Landfill Unit	\$9,444,252	\$6,025,800	\$15,470,052							
Liquid Solidification Unit	11/									
and Citizens Convenience										
Center	\$40,994									
			,							
TOTAL:	\$9,485,246	\$6,025,800	\$15,511,046							

Note: All calculations are carried to full decimal values but numbers are shown rounded.

Closure Costs

Pescadito Environmental Resource Center

Permitted Waste Area: Acres = 660.7 Square Feet = 28,780,092 Largest Area to be closed: Acres = 88 Square Feet = 3,833,280

Unit	1	Unit Cost	Quantity		Cost		
acre	\$	45.00	660.7	\$	29,732		
acre	\$	310	88	\$	27,280		
acre	\$	5,500	88	\$	484,000		
LS	\$	9,500	1	\$	9,500		
				\$	550,512		
					•		
су	\$	5.00	82,817.78	\$	414,089		
су	\$	3.00	354,933.33	\$	1,064,800		
SF	\$	0.50	3,833,280.00	\$	1,916,640		
SF	\$	0.60	3,833,280.00	\$	2,299,968		
су	\$	3.00	141,973	\$	425,920		
acre	\$	1,750.00	88	\$	154,000		
acre	\$	2,600.00	88	\$	228,800		
acre	\$	15,000.00	88	\$	1,320,000		
су	\$	18.50	1,800	\$	33,300		
су	\$	3.00	1,800	\$	5,400		
Trip	\$	165.00	10	\$	1,650		
LS	\$	1,000.00	1	\$	1,000		
LS	\$	5,000.00	1	\$	5,000		
				\$	7,870,567		
		10%		\$	787,057		
		2%		\$	157,411		
		1%		\$	78,706		
ts				\$	1,023,174		
				\$	8,893,741		
TOTAL CLOSURE COSTS:							
	acre acre acre LS cy cy SF SF cy acre acre cy cy LS LS ts	acre \$ acre \$ acre \$ acre \$ acre \$ LS \$ cy \$ cy \$ SF \$ SF \$ cy \$ acre \$	acre \$ 45.00 acre \$ 310 acre \$ 5,500 LS \$ 9,500 Cy \$ 5.00 cy \$ 3.00 SF \$ 0.50 SF \$ 0.60 cy \$ 3.00 acre \$ 1,750.00 acre \$ 2,600.00 acre \$ 15,000.00 cy \$ 3.00 Trip \$ 165.00 LS \$ 1,000.00 LS \$ 1,000.00 LS \$ 5,000.00 10% 2% 11% ts	acre \$ 45.00 660.7 acre \$ 310 88 acre \$ 5,500 88 LS \$ 9,500 1 cy \$ 5.00 82,817.78 cy \$ 3.00 354,933.33 SF \$ 0.50 3,833,280.00 cy \$ 3.00 141,973 acre \$ 1,750.00 88 acre \$ 2,600.00 88 acre \$ 15,000.00 88 cy \$ 18.50 1,800 cy \$ 3.00 148.00 Trip \$ 165.00 10 LS \$ 1,000.00 1 LS \$ 5,000.00 1	acre \$ 45.00 660.7 \$ acre \$ 310 88 \$ acre \$ 5,500 88 \$ \$ LS \$ 9,500 1 \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$		

Notes:

- 1. Surveying costs is based on 660.7 ac permit area, while other costs are based on closure area
- 2. Final Cover Costs are based on utilizing the permitted WB Final Cover System and onsite soil.
- 2. Geomembrane and geosynthetic drain will be used only over Class 1 cells. Cover will utilize onsite soil.
- 3. Vegetation includes watering until vegetation is established
- 4. Storm Water Control includes construction of storm water storage pond
- 5. Assume materials from liquid stabilization and citizen convenience center will be disposed in landfill
- 6. Contaminated water storage will be closed and decommissioned during post-closure period